

CHITALDRUG DIVISION.

The 3rd April 1899.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug Division, up to 30th April 1899, for constructing a new Taluk Cutcherry at Davangere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1901.

2. The plans and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees three hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a new Taluk Cutcherry at Davangere" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

<i>Description of work.</i>	<i>Unit of work.</i>	<i>Quantity.</i>
Earthwork excavation	C. yds.	1,464
Concrete foundation	C. ft.	5,71
Burnt stone in mortar (foundation)	"	13,533
Burnt brick in mortar (superstructure)	"	20,318
Do archwork	"	291
Stone slabs dressed roughly	S. ft.	1,909
Gothic cornice.	R. ft.	169
Cornice 9" deep	"	806
Perforated parapet wall	"	70
String course	"	364
Pointing	Sqrs.	13.76
Plastering with chunam	"	359.19
Mangalore tile flooring over concrete bed pointed with cement	"	62.70
White-washing and color-washing Kadapa stone flagging with painting and dressing.	"	359.19
Gravel flooring	C. yd.	14.00
Bamboo matting, outer rid	"	72
Mangalore tile roofing	Sqrs.	62.59
Terrace roofing	"	90.55
Bengal terrace roofing	"	1.49
Corrugated iron roofing	"	42.92
Teak wood ceiling ½" thick	"	1.11
Zinc gutters, vally	"	9.44
Teak wood work	No.	8
Teak wood pannelled doors	C. ft.	1,066
Do battened doors	S. ft.	614
Iron door for Treasury	"	91
Gate for main entrance	No.	1
Windows with iron bars with battened shutters	"	1
Do pannelled with glazed shutters, iron bars, &c.	S. ft.	2
Cut stone base to wooden pillars	No.	724
Ventilators with iron bars and perforated zinc	"	24
Ventilators, glazed	S. ft.	19
Ventilators in front of gables	No.	430
Painting	Sqrs.	4
Ornamental wooden railings	R. ft.	42.3
Moulding and complete at entrance	Lump sum.	9
Ornamental finials	No.	7
Dais with railing, complete	Lump sum.	
Prisoners' dock and witness box, complete	"	
Clearing site and levelling ground	"	
Fencing and hedging for compound round Taluk Cutcherry	"	
Wood-oiling to wood work	"	

K. PRAHLADA RAO,
Executive Engineer.